

AD-A105 301

HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE F/G 13/13  
NATIONAL DAM SAFETY PROGRAM, KELLER LAKE DAM (MO 11608), MISSOU--ETC(U)  
JUN 80 R S DECKER, G JAMISON, G ULMER DACW43-80-C-0071

UNCLASSIFIED

NL

1 OF  
434  
106301

END  
DATE  
FILMED  
10-81  
DTIC

**LEVEL II**



**MISSOURI-NEMAHA-NODAWAY BASIN**

AD A105301

**KELLER LAKE DAM**

**ANDREW COUNTY, MISSOURI**

**MO. 11608**

**PHASE 1 INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM**



**United States Army  
Corps of Engineers**

*...Serving the Army  
...Serving the Nation*

**St. Louis District**

**PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS**

**FOR: STATE OF MISSOURI**

**DTIC  
ELEC  
S OCT 9 1981 D**

**JUNE, 1980**

**DISTRIBUTION STATEMENT A**

**Approved for public release;  
Distribution Unlimited**

**81 10 7 103**

PREPARE COPY

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO. AD-A105	3. RECIPIENT'S CATALOG NUMBER 301
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Keller Lake Dam (MO 11608) Andrew County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report.
7. AUTHOR(s) Hoskins-Western-Sonderegger, Inc.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) DACW43-80-C-0071
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) National Dam Safety Program, Keller Lake Dam (MO 11608), Missouri - Nemaha - Nodaway Basin, Andrew County, Missouri. Phase I Inspection Report.		12. REPORT DATE June 1980
		13. NUMBER OF PAGES Approximately 70
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
16. DISTRIBUTION STATEMENT Approved for release; distribution unlimited.		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

## INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

**RESPONSIBILITY.** The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

**CLASSIFICATION.** Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

### COMPLETION GUIDE

**General.** Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

**Block 1.** Report Number. Enter the unique alphanumeric report number shown on the cover.

**Block 2.** Government Accession No. Leave Blank. This space is for use by the Defense Documentation Center.

**Block 3.** Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

**Block 4.** Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

**Block 5.** Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

**Block 6.** Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

**Block 7.** Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

**Block 8.** Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

**Block 9.** Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

**Block 10.** Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

**Block 11.** Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

**Block 12.** Report Date. Enter here the day, month, and year or month and year as shown on the cover.

**Block 13.** Number of Pages. Enter the total number of pages.

**Block 14.** Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

**Blocks 15 & 15a.** Security Classification of the Report; Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

**Block 16.** Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 17.** Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 18.** Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with . . . Translation of (or by) . . . Presented at conference of . . . To be published in . . .

**Block 19.** Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

**Block 20.** Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.

KELLER LAKE DAM  
ANDREW COUNTY, MISSOURI  
MISSOURI IDENTIFICATION NO. MO.11608

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

PREPARED BY  
HOSKINS-WESTERN-SONDEREGGER, INC.  
CONSULTING ENGINEERS  
LINCOLN, NEBRASKA

UNDER DIRECTION OF  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS  
FOR

GOVERNOR OF MISSOURI

JUNE, 1980

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	

DTIC  
ELECTE  
OCT 9 1981  
S D



READY TO  
ATTENTION OF

**DEPARTMENT OF THE ARMY**  
**ST. LOUIS DISTRICT, CORPS OF ENGINEERS**  
210 TUCKER BOULEVARD, NORTH  
ST. LOUIS, MISSOURI 63101

SUBJECT: Keller Lake Dam - MO 11608

This report presents the results of field inspection and evaluation of the Keller Lake Dam. It was prepared under the National Program of Inspection of Non-Federal Dams.

SUBMITTED BY:

**SIGNED**

Chief, Engineering Division

25 SEP 1980

Date

APPROVED BY:

**SIGNED**

Colonel, CE, District Engineer

~~27 SEP 1980~~

Date

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

TABLE OF CONTENTS

<u>PARAGRAPH NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
	Assessment Summary	
	Overview Photograph	
	SECTION 1 - PROJECT INFORMATION	
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	2
	SECTION 2 - ENGINEERING DATA	
2.1	Design	5
2.2	Construction	5
2.3	Operation	5
2.4	Evaluation	5
	SECTION 3 - VISUAL INSPECTION	
3.1	Findings	6
3.2	Evaluation	8
	SECTION 4 - OPERATIONAL PROCEDURES	
4.1	Procedures	9
4.2	Maintenance of Dam	9
4.3	Maintenance of Operating Facilities	9
4.4	Description of Any Warning System in Effect	9
4.5	Evaluation	
	SECTION 5 - HYDRAULIC/HYDROLOGIC	
5.1	Evaluation of Features	10
	SECTION 6 - STRUCTURAL STABILITY	
6.1	Evaluation of Structural Stability	11
	SECTION 7 - ASSESSMENT/REMEDIAL MEASURES	
7.1	Dam Assessment	12
7.2	Remedial Measures	12



## APPENDIX A - MAPS

Plate A-1	Vicinity Topography
Plate A-2	Location Map

## APPENDIX B - PHOTOGRAPHS

Plate B-1	Photo Index	
Plate B-2	Photo No. 2	Upstream Face Taken From Left End. Well Covered With Old Concrete Rubble
	Photo No. 3	Crest Taken From Left End
Plate B-3	Photo No. 4	Looking Left to Right Along the Downstream Crest at Two Power Poles Which are Off Vertical About 5° to 10°
	Photo No. 5	Repair Work on Upstream Face at About Sta. 2+70 to 3+00
Plate B-4	Photo No. 6	Looking Downstream on the Backslope Showing the Cow Path
	Photo No. 7	Downstream Slope Taken From Left End. Slope Almost Completely Covered With Trees and Rubbish. Trees up to 12 to 15 Inches in Diameter
Plate B-5	Photo No. 8	Looking Upstream in the Emergency Spillway
	Photo No. 9	Looking Downstream the Emergency Spillway Which Drains Into a Low Terrace and Into an Adjoining Small Reservoir
Plate B-6	Photo No. 10	Glacial Till Outcropping Along Right Shoreline Just Upstream From the Right End of Dam
	Photo No. 11	Looking Upstream at About Sta. 4+30
Plate B-7	Photo No. 12	Looking Downstream From About Sta. 4+30. Note the Other Small Lake Just Downstream of Keller Lake
	Photo No. 13	Overview From Left Side
Plate B-8	Photo No. 14	Overview From North End
	Photo No. 15	6' x 6' Culvert Under Interstate 29

## APPENDIX C - PROJECT PLATES

Plate C-1	Phase I - Plan of Dam and Profile Along Centerline of Dam
Plate C-2	Phase I - Maximum Section of Dam and Profile Along Centerline of Spillway
Plate C-3	Phase I - Section of Spillway along Centerline of Dam and Section of Spillway Appro- ximately 100' Downstream

## APPENDIX D - HYDRAULIC AND HYDROLOGIC DATA

Plates D-1 and D-2	Hydrologic Computations
Plate D-3	Spillway Discharge Rating Curve
Plates D-4 through D-25	Computer Input and Output for Ratios of the PMF

PHASE I REPORT  
NATIONAL DAM SAFETY PROGRAM  
ASSESSMENT SUMMARY

Name of Dam	Keller Lake Dam
State Located	Missouri
County Located	Andrew County
Stream	Tributary to Dillon Creek
Date of Inspection	June 2, 1980

Keller Lake Dam was inspected by an interdisciplinary team of engineers ~~from Hoskins-Western-Sonderregger, Inc.~~ The purpose of the inspection was to make an assessment of the general conditions of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.

The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers and developed with the help of several Federal and State agencies, professional engineering organizations, and private engineers.

Keller Lake Dam has a height of twenty-five(25) feet and a storage capacity at the minimum top elevation of the dam of forty-three (43) acre-feet. In accordance with the guidelines, a small size dam has a height greater than or equal to twenty-five (25) feet but less than forty (40) feet and a storage capacity greater than or equal to fifty (50) acre-feet but less than one thousand (1,000) acre-feet. The size classification is determined by either the storage capacity or height, whichever gives the larger size category. Keller Lake Dam is classified as a small size dam.


In accordance with the guidelines and based on visual observation, dam is classified as having a high potential for damage and loss of life. Failure would threaten life and property. The estimated damage zone extends about one mile downstream of the dam. Within the damage zone are two small lakes and dams, eleven trailer homes and Highway I-29.

Our inspection and evaluation indicates that the spillways meet the criteria set forth in the recommended guidelines for a small dam having a high hazard potential. Considering the small volume of water impounded, one-half of the Probable Maximum Flood is the appropriate spillway design flood. The spillways will pass the 100-year flood (1% probability flood, a flood having a one percent chance of being exceeded in any year) without overtopping the dam. The spillways will pass 80% of the Probable Maximum Flood without overtopping the dam. The Probable Maximum Flood (PMF) is defined as the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

No design data were available for this dam. Based on the observation made during the field inspection of the dam. This dam is considered to be structurally and hydrologically adequate and safe.

The following recommendations are made in regard to maintenance of the dam:

- a. The willow trees and brush should be removed from the upstream slope.
- b. Trees and brush up to 12 to 14 inches in diameter should be removed from the downstream slope under the guidance of an engineer experienced in the design and construction of dams and a good vegetative cover reestablished.
- c. A program of regular inspection and maintenance should be initiated with particular emphasis on the removal and/or control of the tree growth on the slopes.




Rey S. Decker  
E-3703



Gordon Jamison



Garold Ulmer  
E-19246



Harold P. Hoskins, Chairman of the Board  
Hoskins-Western-Sonderregger, Inc.  
E-8696



PHOTO NO. 1 - OVERVIEW

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
KELLER LAKE DAM - MO 11608  
ANDREW COUNTY, MISSOURI

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

- a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, District Engineer directed that a safety inspection of Keller Lake Dam be made.
- b. Purpose of Inspection. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.
- c. Evaluation Criteria. Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams", Appendix D to "Report of the Chief of Engineers on the National Program of Inspection of Dams," dated May, 1975, and published by the Department of the Army, Office of the Chief of Engineers.

1.2 DESCRIPTION OF PROJECT

- a. Description of Dam and Appurtenances.
  - (1) The dam is an earth fill approximately 425 feet in length and 25 feet in height. The maximum water storage at the minimum top of dam is 43 acre-feet. This site is located in the dissected till plains area of the Central Lowlands Physiographic Region.
  - (2) The spillway is an uncontrolled earth channel cut through the right abutment. A seven-inch diameter cast iron pipe culvert approximately 23 feet in length crosses under the gravelled road control section spanning the spillway.
  - (3) Pertinent physical data are given in paragraph 1.3 below.
- b. Location. The dam is located in the south central portion of Andrew County, Missouri, as shown on Plate A-2. The dam is shown on Plate A-1 in the SE 1/4 of Section 3, T 58 N, R 35 W.
- c. Size Classification. Criteria for determining the size classification of dams and impoundments are presented in the guidelines referenced in paragraph 1.1c above. Keller Lake Dam has a height of 25 feet and a storage capacity at the minimum top elevation of the dam of 43 acre-feet. This dam is classified as a small size dam. A small size dam has a height greater than or equal to 25 feet but less than 40 feet and a storage capacity greater than or equal to 50 acre-feet but less than 1,000 acre-feet. The size classification is determined by either the storage capacity or height, whichever gives the larger size category.

- d. Hazard Classification. Guidelines for determining hazard classification are presented in the same guidelines as referenced in paragraph 1.1c above. Based on referenced guidelines and visual observation, this dam is in the High Hazard Classification. The estimated damage zone extends about one mile downstream of the dam. Within the damage zone are two small lakes and dams, eleven trailer homes and Highway I-29.
- e. Ownership. The dam is owned by Mr. A. J. Keller, Route 3, St. Joseph, Missouri 64505.
- f. Purpose of Dam. The dam was constructed to impound water to be used by a ready-mix concrete plant owned by Mr. A. J. Keller. The concrete plant was sold in 1968, and the reservoir no longer is used for its original purpose.
- g. Design and Construction History. The dam was constructed in 1963 by Mr. A. J. Keller who stated that a core trench was excavated six feet into clay. Materials for the embankment were borrowed from the abutments and were compacted with sheepsfoot rollers. A 2 1/2-inch pipeline was constructed through the left end of the dam to carry water from the reservoir to the concrete plant.
- h. Normal Operating Procedure. There are no controlled outlets for this dam other than the 2 1/2-inch pipeline formerly used to transport water to the concrete plant. The level of the pool is dependent upon precipitation, infiltration, evaporation, and the capacity of the uncontrolled spillway.

### 1.3 PERTINENT DATA

- a. Drainage Area. 31.3 acres (0.049 acres).
- b. Discharge At Damsite.
  - (1) All discharges at the damsite are through an uncontrolled vegetated earth spillway cut through the right abutment with a gravel covered road normal to the spillway acting as a weir. There is a 7-inch diameter cast iron pipe acting as a culvert under the road that discharges into the spillway channel.
  - (2) Estimated maximum flood at damsite--- It was reported by Mr. A. J. Keller that the maximum discharge through the spillway produced an approximate depth of 1 foot of water in the spillway. It was not reported when that occurred.
  - (3) The spillway capacity varies from 0 c.f.s. at its crest (elevation 1018.0 feet) to 327 c.f.s. at the minimum top of dam (elevation 1019.7 feet).
  - (4) Total spillway capacity at the minimum top of dam is 327 c.f.s.  $\pm$

c. Elevations. (Feet above M.S.L.)

- (1) Top of dam - 1019.7 (minimum)
- (2) Spillway crest - 1018.0 (crest of road);  
1017.5 (invert of 7-inch diameter culvert)
- (3) Observed pool - 1017.2
- (4) Normal pool - 1017.5
- (5) Maximum experienced pool - 1018.5  $\pm$
- (6) Streambed at centerline - 994.5
- (7) Maximum tailwater - Unknown

d. Reservoir. Length (feet) of pool

- (1) Spillway Crest - 600  $\pm$
- (2) Top of Dam (minimum) - 700 $\pm$

e. Storage (Acre-feet).

- (1) Top of dam - 43  $\pm$
- (2) Spillway crest - 34  $\pm$
- (3) Observed pool - 34  $\pm$
- (4) Normal pool - 34  $\pm$
- (5) Maximum experienced pool - 35  $\pm$

f. Reservoir Surface (Acres).

- (1) Top of dam - 6  $\pm$
- (2) Spillway crest - 4  $\pm$
- (3) Observed pool - 4  $\pm$
- (4) Normal pool - 4  $\pm$
- (5) Maximum experienced pool - 5  $\pm$

g. Dam.

- (1) Type - Earth fill
- (2) Length - 425 ft.  $\pm$
- (3) Height - 25 ft.  $\pm$
- (4) Top width - 15 ft.  $\pm$

(5) Side slopes.

(a) Downstream - 1V on 2.1 H, 1V on 3.3 H, 1V on 1.6 H  
(avg. 1V on 2 H)

(b) Upstream - 1V on 1.3 H (exposed)

(6) Zoning - unknown

(7) Impervious core - Core trench excavated 6 feet into clay (reported by Mr. A. J. Keller).

(8) Cutoff - unknown

(9) Grout curtain - unknown

(10) Wave protection - concrete rubble riprap

(11) Drains - none

h. Diversion Channel and Regulating Tunnel. None

i. Spillway.

(1) Principal (and only)

(a) Type - Vegetated earth, uncontrolled spillway cut through right abutment with a 7-inch diameter cast iron pipe culvert under the gravel surfaced road that crosses the spillway.

(b) Control section - gravel surfaced road crossing the spillway acting as a weir.

(c) Crest elevation - 1018.0 (minimum road surface elevation)

(d) Upstream Channel - clear of vegetation. Water surface at the upstream end of the 7-inch culvert. Slope of channel unknown.

(e) Downstream Channel - Channel excavated in a hillside in a westerly direction from the right end of the dam approximately 500 feet where it discharges into a small reservoir.

j. Regulating Outlets. None



## SECTION 2 - ENGINEERING DATA

### 2.1 DESIGN

No design data were available for this dam.

### 2.2 CONSTRUCTION

No construction data were available. Mr. A. J. Keller reported that he had constructed the dam in 1963 and that a core trench had been excavated to a depth of six feet into clay. It was also reported that the embankment materials were borrowed from the abutments and that compaction was done with sheepsfoot rollers.

### 2.3 OPERATION

No data were available on spillway operation. It was reported by Mr. A. J. Keller that the maximum discharge in the spillway produced an approximate depth of one foot of water in the spillway.

### 2.4 EVALUATION

- a. Availability. No data were available
- b. Adequacy. The field surveys and visual observations presented herein are considered adequate to support the conclusions of this report. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.
- c. Validity. Not applicable.

## SECTION 3 - VISUAL INSPECTION

### 3.1 FINDINGS

- a. General. A visual inspection of the Keller Lake Dam was made on June 2, 1980. Engineers from Hoskins-Western-Sonderregger, Inc., Lincoln, Nebraska making the inspection were: R. S. Decker, Geotechnical, Garold Ulmer and Gordon Jamison, Hydrology and Hydraulics. The owner, Mr. A. J. Keller, was interviewed prior to the inspection but was not present during the inspection.

b. Dam.

- (1) Geology and Soils (abutment and embankment). Keller Lake Dam is located in the dissected till plains area within the Central Lowlands Physiographic Region. The dam site is in a region where the stratigraphic sequence consists of loess, 4 to 8 feet thick, overlying Kansan-age glacial drift, of undetermined thickness and character which in turn overlies bedrock. Bedrock beneath the site consists of strata assigned to the Pedee and Lansing Groups, Missourian Series, Pennsylvanian System. Strata of these two groups are comprised of interlayered sequences of shale, sandstone, and limestone.

The upland soils in the dam area consists of soils of the Knox-Marshall soil association. This soil association is common in the dissected areas adjacent to the Missouri River where soils are formed on deep loess deposits. They are positioned on rolling to hilly topography with the Knox soils occupying the steeper slopes and narrow ridgetops. The Marshall soil occupies the more gently sloping areas. Both soils have a moderate infiltration rate.

The abutments consist of loess colluvium overlying glacial till. Till (gravelly CH) is exposed along the shoreline on the right side of the reservoir (See Photo No. 10) Materials in the valley consist of alluvium of unknown depth. Materials in the dam are CL-CH borrowed from the loess-till abutments.

- (2) Upstream Slope. The upstream slope is pretty well covered with concrete rubble riprap. No erosion was noted. A few small trees and brush are growing along the waterline. No bulges or slumps were observed. Some loose dirt had been recently placed along the upstream face in the area of station 2 + 70 to 3 + 00. The reason for this new fill is not known. Photo No. 2 shows the upstream slope and Photo No. 5 the recent repair work on the slope.
- (3) Crest. The crest is well vegetated with adapted grasses and legumes. Measurements indicate that the crest elevation is quite uniform. A section of the upstream crest (and upstream slope) between centerline station 2 + 70 and 3 + 00 had been recently filled with soil as shown in Photo No. 5. No cracks

were observed on the crest. No bulges were observable along the crest, but two utility poles on the crest lean downstream at about 5 to 10 degrees off vertical. The crest and leaning poles are shown in Photo 3, 4 and 5.

- (4) Downstream Slope. The downstream slope is well covered with brush and trees up to 12 to 14 inches in diameter. There is a sparse cover of grass beneath the trees. No significant erosion was noted. The downstream slope is shown in Photos 3, 4 & 7. A berm-like projecting or slump occurs on the downstream slope about 10 feet vertically below the crest, from about centerline station 1 + 75 to 3 + 50. It is not known whether this was a constructed berm or is the result of bulging and/or spreading of the embankment. Although the power poles on the crest are leaning downstream, the trees on the downslope in this area do not appear to be misaligned. At the present time it appears to be stable and is used as a cow path. This area is shown in Photo No. 6.

A small seepage area was observed in the lower end of the right abutment trough. There was no visible discharge from this seep.

c. Appurtenant Structures.

- (1) Spillway- The uncontrolled spillway consists of a cut through the right abutment. It has a bottom width of 35 feet  $\pm$  with side slopes of 1V on 12 H or flatter. A roadway, that appeared relatively new, was constructed across the spillway. A 7-inch cast iron pipe passed through the base of the roadway. An old conservation terrace serves as the outlet for the spillway. This terrace goes around the ridge into an adjacent drainage way. The first 80 to 100 feet of outlet channel immediately downstream from the roadway has been recently denuded of vegetation. The terrace channel downstream from this area is well vegetated with adapted grasses. The entrance section is open and clear. Photos 8 & 9 show the spillway.
- (2) Drawdown Facility- Mr. A. J. Keller reported that there is a 2 1/2-inch steel pipeline passing through the left end of the dam that was used as a water supply for the concrete ready-mix plant. The concrete plant is now dismantled, and this pipeline has not been used for several years.

- d. Reservoir Area. The area around the reservoir is well grassed, and there was no erosion apparent along the waterline. Mr. A. J. Keller reported that a permanent spring along the west side feeds into the reservoir. Photo No. 11 shows a portion of the reservoir.

- e. Downstream Channel. The downstream channel from the spillway does

not enter the old channel downstream from the dam. The channel is excavated in a hillside leading to the west approximately 500 feet where it discharges into a small reservoir. Photo No. 1 shows a portion of the small reservoir at the extreme left center. The channel is devoid of vegetative growth for a distance of 80 to 100 feet downstream from the gravelled road that serves as the spillway control section, and the raw appearance would indicate recent construction. The remainder of the channel has good vegetative growth with no trees or brush. Photos 8 and 9 show views of the channel immediately downstream from the control section.

### 3.2 EVALUATION

This dam is in reasonably good shape with no serious potential of failure. The slight seepage in the right abutment trough has no apparent detrimental effect upon the integrity of the dam. The cause of the irregularities (berm, slump or what) in the downstream slope and the leaning power poles is not known; however, there is no evidence of recent deformation on the slope (trees on the slope, up to 12 inches in diameter, appear to be near vertical). Tree growth on the downstream slope could ultimately impair the integrity of the dam.

## SECTION 4 - OPERATIONAL PROCEDURES

### 4.1 PROCEDURES

The only controlled outlet for this dam is the 2 1/2-inch pipe that formerly carried water from the reservoir to the concrete plant. The pool level is controlled by rainfall, infiltration, evaporation, and the capacity of the uncontrolled spillway.

### 4.2 MAINTENANCE OF DAM

The extensive tree growth on the downstream slope of the dam would indicate some deficiency in maintenance operations.

### 4.3 MAINTENANCE OF OPERATING FACILITIES

No operating facilities exist at this dam other than the 2 1/2-inch pipe that formerly carried water from the reservoir to the concrete plant. The concrete plant is no longer in use.

### 4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

There is no warning system in effect for this dam.

### 4.5 EVALUATION

The majority of deficiencies observed during the inspection were due to a lack of routine maintenance.

## SECTION 5 - HYDRAULIC/HYDROLOGIC

### 5.1 EVALUATION OF FEATURES

- a. Design Data. No design data were found for this dam.
- b. Experience Data. The drainage area, reservoir surface area, and elevation-storage data were developed from the USGS St. Joseph North, Missouri, 7.5 minute topographic quadrangle map. The hydraulic computations for the spillway and dam overtopping discharge ratings were based on data collected in the field at the time of the field inspection.
- c. Visual Observations.
  - (1) The spillway is cut through the right abutment and discharges into a terrace which drains into an adjoining small reservoir (See Photo No. 1). Spillway releases will not endanger the integrity of the dam.
  - (2) A road over the spillway with a 7-inch pipe culvert appeared to have been recently constructed.
  - (3) It is reported by Mr. A. J. Keller that there is a 2 1/2-inch drawdown pipe through the dam which had been used as a water supply for a concrete plant in the past. The pipe was not located during the inspection.
- d. Overtopping Potential. The spillways are too small to pass the probable maximum flood without overtopping. The spillways will pass the 1% probabilistic flood as well as 80% of the probable maximum flood without overtopping the dam. The overtopping which the embankment would experience during the PMF is such that it should not cause excessive damage. The results of the routings through the dam are tabulated in regards to the following conditions:

Frequency	Inflow Discharge c.f.s.	Outflow Discharge c.f.s.	Maximum Pool Elevation	*Maximum Depth Over Dam, Ft.	Duration Over Top Hr.
1/2 PMF	270	190	1019.3	0	0
PMF	550	430	1019.9	0.2	1-
0.80 PMF	440	320	1019.7	0	0

\*Minimum top of dam elevation - 1019.7

According to the recommended guidelines from the Department of the Army, Office of the Chief of Engineers, this dam is classified as having a high hazard rating and a small size. Therefore, the 1/2 PMF to the PMF is the test for the adequacy of the dam and its spillway.

The estimated damage zone is described in Paragraph 1.2d in this report.

## SECTION 6 - STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observation. This dam appears to be structurally stable from the standpoint of strength and excess seepage pressures. Any deformation processes that could have caused the irregularities in the downstream slope have evidently stabilized. The dam has been in place with full reservoir for 17 years, and there is no evidence of recent movements of slides on the downstream slope. Uncontrolled tree growth on the downstream slope might ultimately affect the safety of the structure.
- b. Design and Construction Data. No design or construction data were available. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- c. Operating Records. There are no controlled operating facilities for this dam other than the 2 1/2-inch water line which formerly carried water from the reservoir to the concrete plant.
- d. Post Construction Changes. It would appear that the road crossing the spillway has been constructed rather recently.
- e. Seismic Stability. This dam is located in Seismic Zone 1. An earthquake of magnitude predicted in this area is not expected to cause structural failure of this dam.

## SECTION 7- ASSESSMENT/REMEDIAL MEASURES

### 7.1 DAM ASSESSMENT

- a. Safety. This dam is in reasonably good condition except for extensive tree growth on the downstream slope and a few small willows on the upstream slope. It is considered to be structurally stable. It is hydrologically adequate to pass 80% of the probable maximum flood (PMF) without overtopping and the PMF storm will only overtop the dam by 0.2 foot + for about 1 hour which should not cause extensive damage to the embankment.

This dam does not appear to have any serious potential of failure. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available which is considered a deficiency.

- b. Adequacy of Information. Due to the lack of engineering data, the conclusions in this report are based upon performance history and visual observations. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available which is considered a deficiency.
- c. Urgency. There does not appear to be any urgency to accomplish the remedial measures recommended in paragraph 7.2.
- d. Necessity for Further Investigations. Further investigations are not considered necessary.
- e. Seismic Stability. This dam is located in Seismic Zone 1. An earthquake of this magnitude is not expected to be hazardous to this dam.

### 7.2 REMEDIAL MEASURES

- a. Alternatives.


- (1) Since the dam and spillway pass 80 percent of the PMF and are in relatively good condition, no alternative methods of accommodating the PMF are required.

- b. Operation and Maintenance Procedures.

- (1) The willow trees and brush should be removed from the upstream slope.
- (2) Trees and brush up to 12 to 14 inches in diameter should be removed from the downstream slope under the guidance of an engineer experienced in the design and construction of dams. A good vegetative cover should be reestablished.
- (3) A program of regular inspection and maintenance should be initiated with particular emphasis on the removal and/or control of tree growth on the slopes.



APPENDIX A  
MAPS



Scale in feet  
2000 1000 0 2000 4000

Contour Interval - 20'





## VICINITY TOPOGRAPHY

KELLER LAKE DAM


ANDREW COUNTY, MISSOURI

MO. 11608

PLATE A-1




VICINITY MAP  
ID NO. MO 11608  
ANDREW COUNTY, MISSOURI



LOCATION MAP  
PLATE A-2

APPENDIX B  
PHOTOGRAPHS



KELLER LAKE DAM  
ANDREW COUNTY, MISSOURI  
MO 11608

PHOTO INDEX

PLATE B-1



PHOTO NO. 2 - UPSTREAM FACE TAKEN FROM LEFT END. WELL  
COVERED WITH OLD CONCRETE RUBBLE



PHOTO NO. 3 - CREST TAKEN FROM LEFT END



PHOTO NO. 4 - LOOKING LEFT TO RIGHT ALONG THE DOWNSTREAM CREST AT TWO POWER POLES WHICH ARE OFF VERTICAL ABOUT 5° to 10°



PHOTO NO. 5 - REPAIR WORK ON UPSTREAM FACE AT ABOUT STA. 2+70 to 3+00




PHOTO NO. 6 - LOOKING DOWNSTREAM ON THE BACKSLOPE SHOWING  
THE COW PATH




PHOTO NO. 7 - DOWNSTREAM SLOPE TAKEN FROM LEFT END. SLOPE  
ALMOST COMPLETELY COVERED WITH TREES & RUBBISH. TREES UP TO  
12 TO 15 INCHES IN DIAMETER





PHOTO NO. 8 - LOOKING UPSTREAM IN THE EMERGENCY SPILLWAY



PHOTO NO. 9 - LOOKING DOWNSTREAM THE EMERGENCY SPILLWAY WHICH DRAINS INTO A LOW TERRACE & INTO AN ADJOINING SMALL RESERVOIR



PHOTO NO. 10 - GLACIAL TILL OUTCROPPING ALONG RIGHT SHORELINE JUST  
UPSTREAM FROM THE RIGHT END OF DAM



PHOTO NO. 11 - LOOKING UPSTREAM AT ABOUT STA. 4+30



PHOTO NO. 12 - LOOKING DOWNSTREAM FROM ABOUT STA. 4+30. NOTE THE OTHER SMALL LAKE JUST DOWNSTREAM OF KELLER LAKE



PHOTO NO. 13 - OVERVIEW FROM LEFT SIDE



PHOTO NO. 14 - OVERVIEW FROM NORTH END







PHOTO NO. 15 - 6' x 6' CULVERT UNDER INTERSTATE 29


APPENDIX C  
PROJECT PLATES







MAXIMUM SECTION OF DAM AT STATION 2+78 (SECTION A-A)

Scale:  $1'' = 10' H$ ;  $1'' = 10 V$ .



### PROFILE ALONG CENTERLINE OF SPILLWAY

Scale:  $1'' = 20'H$ ;  $1'' = 2'V$ .






APPENDIX D  
HYDRAULIC AND HYDROLOGIC DATA

## HYDROLOGIC COMPUTATIONS

1. The SCS dimensionless unit hydrograph and the systemized computer program HEC-1 (Dam Safety Version), July 1978, prepared by the Hydrologic Engineering Center, U.S. Corps of Engineers, Davis, California, were used to develop the inflow hydrographs (See this Appendix).
  - a. Twenty-four hour, one percent probabilistic rainfall for the dam location was taken from the data for the rainfall station at Sweet Springs, Mo. as supplied by the St. Louis District, Corps of Engineers per their letter dated 4 March 1980. The twenty-four probable maximum precipitation was taken from the curves of Hydrometeorological Report No. 33 and current Corps of Engineers and St. Louis policy and guidance for hydraulics and hydrology. The rainfall distribution as described by EM 1110-2-1411 (Standard Project Storm) was used in distributing the rainfall.
  - b. Drainage area = 0.049 square miles (31.3 acres).
  - c. Time of concentration of runoff = 9.6 minutes (computed from SCS "Upland" method). 900 feet of the watershed is in short grass pasture (overland flow) with an average watershed slope of approximately 6%. The overland flow velocity was assumed to be 1.7 ft/sec. Approximately 575 ft of the watershed course was reservoir. Assuming a mean depth of 10 feet, the velocity through the reservoir was assumed to be 16 ft/sec. Travel time was computed using the equation:  $T_t = l/3600V$ , where  $l$  = length, in feet and  $V$  = velocity.

The time of concentration was verified using the "Kirpich" method. A value of 7.7 minutes was obtained. The SCS "Upland" method value was used due to the large amount of overland flow in lieu of small gully flow.
  - d. The antecedent storm conditions for the probable maximum precipitation were heavy rainfall and low temperatures which occurred on the previous 5 days (SCS AMC III). The antecedent storm conditions for the one percent probabilistic precipitation were an average of the conditions which have preceded the occurrence of the maximum annual flood on numerous watersheds (SCS AMC II). The initial pool elevation was assumed at the crest of the spillway. The 7-inch diameter spillway pipe was assumed negligible in relation to the routings due to the antecedent storm preceding the routings.
  - e. The total twenty-four hour storm duration losses for the one percent probabilistic storm were 3.35 inches. The total losses for the PMF storm were 1.87 inches. These data are based on SCS runoff curve No. 86 and No. 71 for antecedent moisture conditions SCS AMC III and AMC II respectively. The watershed is composed of primarily the SCS soil association Marshall-Knox of which both are of hydrologic soil group B. The watershed is mostly in pasture.
  - f. Average soil loss rates = 0.08 inch per hour approximately

- g. The owner stated that the reservoir was spring fed. The spring keeps the lake level about constant; therefore, it replenishes only what the lake loses due to evaporation. With such a small surface area (4-6 acres), evaporation would be minimal. For this reason, the flow into the reservoir from the spring was ignored in the hydrologic routings of the dam.
2. The combined discharge rating consisted of two components: the flow through the spillway and the flow over the top of the dam.
  - a. The spillway discharge rating was developed using methods for flow over Highway Embankments in U.S.G.S. TWRI, BK. 3, Ch. A-5 (coefficients based on h/l ratios and a gravel road surface).
  - b. The flows over the dam crest were developed using the HEC-1 (Dam Safety Version) program using the irregular top of dam option.
3. Floods were routed through the reservoir using the HEC-1 (Dam Safety Version) program to determine the capabilities of the spillway and dam embankment crest. The input, output, and plotted hydrographs are attached in this Appendix.



A1	ANALYSIS UF DAM OVERTOPPING USING RATIOS OF PMF		
A2	HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF KELLER LAKE DAM 11608		
A3	RATIOS OF PMF ROUTED THROUGH THE RESERVOIR		
D	0002880000000000000005		0000000000000000000003
B1	000005		
J	00000100000009000000001		
J1	000.500000.600000.700000.750000.800000.850000.900000.9500001.00		
K	00000000000001		0000000000000000000001
K1	CALCULATION OF INFLOW HYDROGRAPH TO RESERVOIR 11608		00000001
M	0000010000002000.049		0000.049000001.0
P	000000000024.1000001020000012100000130		
T		-1.0	-86.0
W	200000000000.17		
X	000000 - .0100000001		
K	00000100000002	000000200000000000000001	
K1	ROUTED FLOWS THRU RESERVOIR 11608		
Y	000000010000001		
Y1	000001	-1018.0	-1
Y4	1018.0001018.5001019.1001019.7001020.5001021.0001022.0001023.0001024.0001025.0		
Y5	0000000000028.9000140.3000327.4000737.80000108400001912000029880000422700005606		
Y6	0000000000004.25000006.0000014.7		
Y7	0995.0001017.5001020.0001040.0		
Y8	1018.0		
Y9	1019.7000002.9000001.50000425.		
Y10	0000000000052000001950000036000000420000000425000000425		
Y11	1019.7001019.9001020.0001020.2001020.4001020.6001021.0001025.0		
K	000099		

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 26 FEB 79  
 \*\*\*\*\*

RUN DATE= 00/07/16.  
 TIME= 14.45.24.

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF  
 HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF KELLER LAKE DAM 11608  
 RATIOS OF PMF ROUTED THROUGH THE RESERVOIR

JOB SPECIFICATION									
NO	NHR	AMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	INSTAN
28H	0	5	0	0	0	0	0	3	0
JOPER				NMT	LROPT	TRACE			
5				0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIUS= .50 .60 .70 .75 .80 .85 .90 .95 1.00  
 NPLAN= 1 NRTIO= 9 LRTIO= 1

\*\*\*\*\*

SUR-AREA RUNOFF COMPUTATION

CALCULATION OF INFLOW HYDROGRAPH TO RESERVOIR 11608

INHYG	INUG	ITAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	2	.05	0.00	.05	1.00	0.000	0	1	0
PRECIP DATA									
SPFE		PM5	R6	R12	R24	R48	R72	R96	
0.00		24.10	102.00	121.00	130.00	0.00	0.00	0.00	

LOSS DATA				
LROPT	SIRKR	DLTKR	RTIOL	RTIOL
0	0.00	0.00	1.00	1.00
CURVE NO = -86.00 WEIKNSS = -1.00 EFFECT CN = 86.00				

UNIT HYDROGRAPH DATA  
 IC= 0.00 LAG= .17

RECESSION DATA

SIRIC= 0.00 QRESN= -.01 RTICR= 1.00

UNIT HYDROGRAPH 12 ENL OF PERIOD UPDATES, IC= 0.00 HOURS, LAG= .17 VOL= 1.00  
 34. 103. 106. 66. 33. 18. 9. 5. 3. 1.  
 1. 0.

END-13-PERIOD FLOW

MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
1.01	05	1	.01	0.00	.01	0.	1.01	12.05	145	.20	.19	.01	27.
1.01	10	2	.01	0.00	.01	0.	1.01	12.10	146	.20	.19	.01	41.
1.01	15	3	.01	0.00	.01	0.	1.01	12.15	147	.20	.19	.01	55.
1.01	20	4	.01	0.00	.01	0.	1.01	12.20	148	.20	.20	.01	64.
1.01	25	5	.01	0.00	.01	0.	1.01	12.25	149	.20	.20	.01	69.
1.01	30	6	.01	0.00	.01	0.	1.01	12.30	150	.20	.20	.01	71.
1.01	35	7	.01	0.00	.01	0.	1.01	12.35	151	.20	.20	.01	73.
1.01	40	8	.01	0.00	.01	0.	1.01	12.40	152	.20	.20	.01	74.
1.01	45	9	.01	0.00	.01	0.	1.01	12.45	153	.20	.20	.01	74.
1.01	50	10	.01	0.00	.01	0.	1.01	12.50	154	.20	.20	.01	74.
1.01	55	11	.01	0.00	.01	0.	1.01	12.55	155	.20	.20	.01	75.
1.01	1.00	12	.01	0.00	.01	0.	1.01	13.00	156	.20	.20	.01	75.
1.01	1.05	13	.01	0.00	.01	0.	1.01	13.05	157	.25	.24	.01	76.
1.01	1.10	14	.01	0.00	.01	0.	1.01	13.10	158	.25	.24	.01	81.
1.01	1.15	15	.01	0.00	.01	0.	1.01	13.15	159	.25	.24	.01	85.
1.01	1.20	16	.01	0.00	.01	0.	1.01	13.20	160	.25	.24	.01	88.
1.01	1.25	17	.01	0.00	.01	0.	1.01	13.25	161	.25	.24	.01	89.
1.01	1.30	18	.01	0.00	.01	0.	1.01	13.30	162	.25	.24	.01	90.
1.01	1.35	19	.01	0.00	.01	0.	1.01	13.35	163	.25	.24	.01	90.
1.01	1.40	20	.01	0.00	.01	0.	1.01	13.40	164	.25	.24	.01	91.
1.01	1.45	21	.01	0.00	.01	0.	1.01	13.45	165	.25	.24	.01	91.
1.01	1.50	22	.01	0.00	.01	0.	1.01	13.50	166	.25	.24	.00	91.
1.01	1.55	23	.01	0.00	.01	0.	1.01	13.55	167	.25	.24	.00	91.
1.01	2.00	24	.01	0.00	.01	0.	1.01	14.00	168	.25	.24	.00	91.
1.01	2.05	25	.01	0.00	.01	0.	1.01	14.05	169	.31	.30	.01	93.
1.01	2.10	26	.01	0.00	.01	0.	1.01	14.10	170	.31	.30	.01	100.
1.01	2.15	27	.01	0.00	.01	0.	1.01	14.15	171	.31	.30	.00	106.
1.01	2.20	28	.01	0.00	.01	0.	1.01	14.20	172	.31	.30	.00	110.
1.01	2.25	29	.01	0.00	.01	0.	1.01	14.25	173	.31	.30	.00	112.
1.01	2.30	30	.01	0.00	.01	0.	1.01	14.30	174	.31	.30	.00	114.
1.01	2.35	31	.01	0.00	.01	0.	1.01	14.35	175	.31	.30	.00	115.
1.01	2.40	32	.01	0.00	.01	0.	1.01	14.40	176	.31	.30	.00	115.
1.01	2.45	33	.01	0.00	.01	0.	1.01	14.45	177	.31	.30	.00	115.
1.01	2.50	34	.01	0.00	.01	0.	1.01	14.50	178	.31	.30	.00	115.
1.01	2.55	35	.01	0.00	.01	0.	1.01	14.55	179	.31	.30	.00	115.
1.01	3.00	36	.01	0.00	.01	0.	1.01	15.00	180	.31	.30	.00	115.
1.01	3.05	37	.01	0.00	.01	0.	1.01	15.05	181	.19	.18	.00	111.
1.01	3.10	38	.01	0.00	.01	1.	1.01	15.10	182	.37	.37	.00	105.
1.01	3.15	39	.01	0.00	.01	1.	1.01	15.15	183	.37	.37	.00	112.
1.01	3.20	40	.01	0.00	.01	1.	1.01	15.20	184	.56	.56	.01	130.
1.01	3.25	41	.01	0.00	.01	1.	1.01	15.25	185	.65	.65	.01	160.
1.01	3.30	42	.01	0.00	.01	1.	1.01	15.30	186	1.59	1.58	.01	225.
1.01	3.35	43	.01	0.00	.01	1.	1.01	15.35	187	2.62	2.60	.02	374.
1.01	3.40	44	.01	0.00	.01	1.	1.01	15.40	188	1.03	1.02	.01	543.
1.01	3.45	45	.01	0.00	.01	1.	1.01	15.45	189	.65	.65	.00	545.
1.01	3.50	46	.01	0.00	.01	1.	1.01	15.50	190	.56	.56	.00	439.
1.01	3.55	47	.01	0.00	.01	1.	1.01	15.55	191	.37	.37	.00	332.
1.01	4.00	48	.01	0.00	.01	1.	1.01	16.00	192	.37	.37	.00	254.
1.01	4.05	49	.01	0.00	.01	1.	1.01	16.05	193	.29	.29	.00	199.
1.01	4.10	50	.01	0.00	.01	1.	1.01	16.10	194	.29	.29	.00	161.
1.01	4.15	51	.01	0.00	.01	1.	1.01	16.15	195	.29	.29	.00	137.
1.01	4.20	52	.01	0.00	.01	1.	1.01	16.20	196	.29	.29	.00	123.
1.01	4.25	53	.01	0.00	.01	1.	1.01	16.25	197	.29	.29	.00	116.
1.01	4.30	54	.01	0.00	.01	1.	1.01	16.30	198	.29	.29	.00	112.
1.01	4.35	55	.01	0.00	.01	1.	1.01	16.35	199	.29	.29	.00	110.
1.01	4.40	56	.01	0.00	.01	1.	1.01	16.40	200	.29	.29	.00	109.
1.01	4.45	57	.01	0.00	.01	1.	1.01	16.45	201	.29	.29	.00	109.
1.01	4.50	58	.01	0.00	.01	1.	1.01	16.50	202	.29	.29	.00	108.
1.01	4.55	59	.01	0.00	.01	1.	1.01	16.55	203	.29	.29	.00	108.
1.01	5.00	60	.01	0.00	.01	2.	1.01	17.00	204	.29	.29	.00	108.

1.01	5.05	61	-01	-01	-01	2.	1.01	17.05	205	-23	-22	-00	106.
1.01	5.10	62	-01	-01	-01	2.	1.01	17.10	206	-23	-22	-00	100.
1.01	5.15	63	-01	-01	-01	2.	1.01	17.15	207	-23	-22	-00	94.
1.01	5.20	64	-01	-01	-01	2.	1.01	17.20	208	-23	-22	-00	90.
1.01	5.25	65	-01	-01	-01	2.	1.01	17.25	209	-23	-22	-00	87.
1.01	5.30	66	-01	-01	-01	2.	1.01	17.30	210	-23	-22	-00	86.
1.01	5.35	67	-01	-01	-01	2.	1.01	17.35	211	-23	-22	-00	86.
1.01	5.40	68	-01	-01	-01	2.	1.01	17.40	212	-23	-22	-00	86.
1.01	5.45	69	-01	-01	-01	2.	1.01	17.45	213	-23	-22	-00	85.
1.01	5.50	70	-01	-01	-01	2.	1.01	17.50	214	-23	-22	-00	85.
1.01	5.55	71	-01	-01	-01	2.	1.01	17.55	215	-23	-22	-00	85.
1.01	6.00	72	-01	-01	-01	2.	1.01	18.00	216	-23	-22	-00	85.
1.01	6.05	73	-06	-06	-03	3.	1.01	18.05	217	-02	-02	-00	78.
1.01	6.10	74	-06	-06	-03	5.	1.01	18.10	218	-02	-02	-00	57.
1.01	6.15	75	-06	-06	-03	8.	1.01	18.15	219	-02	-02	-00	35.
1.01	6.20	76	-06	-06	-03	10.	1.01	18.20	220	-02	-02	-00	21.
1.01	6.25	77	-06	-06	-03	11.	1.01	18.25	221	-02	-02	-00	15.
1.01	6.30	78	-06	-06	-03	12.	1.01	18.30	222	-02	-02	-00	11.
1.01	6.35	79	-06	-06	-03	13.	1.01	18.35	223	-02	-02	-00	9.
1.01	6.40	80	-06	-06	-04	14.	1.01	18.40	224	-02	-02	-00	8.
1.01	6.45	81	-06	-06	-04	14.	1.01	18.45	225	-02	-02	-00	7.
1.01	6.50	82	-06	-06	-04	15.	1.01	18.50	226	-02	-02	-00	7.
1.01	6.55	83	-06	-06	-04	15.	1.01	18.55	227	-02	-02	-00	7.
1.01	7.00	84	-06	-06	-04	16.	1.01	19.00	228	-02	-02	-00	7.
1.01	7.05	85	-06	-06	-04	16.	1.01	19.05	229	-02	-02	-00	7.
1.01	7.10	86	-06	-06	-05	16.	1.01	19.10	230	-02	-02	-00	7.
1.01	7.15	87	-06	-06	-05	17.	1.01	19.15	231	-02	-02	-00	7.
1.01	7.20	88	-06	-06	-05	17.	1.01	19.20	232	-02	-02	-00	7.
1.01	7.25	89	-06	-06	-05	17.	1.01	19.25	233	-02	-02	-00	7.
1.01	7.30	90	-06	-06	-05	18.	1.01	19.30	234	-02	-02	-00	7.
1.01	7.35	91	-06	-06	-05	18.	1.01	19.35	235	-02	-02	-00	7.
1.01	7.40	92	-06	-06	-05	18.	1.01	19.40	236	-02	-02	-00	7.
1.01	7.45	93	-06	-06	-05	18.	1.01	19.45	237	-02	-02	-00	7.
1.01	7.50	94	-06	-06	-05	19.	1.01	19.50	238	-02	-02	-00	7.
1.01	7.55	95	-06	-06	-05	19.	1.01	19.55	239	-02	-02	-00	7.
1.01	8.00	96	-06	-06	-05	19.	1.01	20.00	240	-02	-02	-00	7.
1.01	8.05	97	-06	-06	-05	19.	1.01	20.05	241	-02	-02	-00	7.
1.01	8.10	98	-06	-06	-05	19.	1.01	20.10	242	-02	-02	-00	7.
1.01	8.15	99	-06	-06	-05	19.	1.01	20.15	243	-02	-02	-00	7.
1.01	8.20	100	-06	-06	-05	20.	1.01	20.20	244	-02	-02	-00	7.
1.01	8.25	101	-06	-06	-05	20.	1.01	20.25	245	-02	-02	-00	7.
1.01	8.30	102	-06	-06	-05	20.	1.01	20.30	246	-02	-02	-00	7.
1.01	8.35	103	-06	-06	-05	20.	1.01	20.35	247	-02	-02	-00	7.
1.01	8.40	104	-06	-06	-05	20.	1.01	20.40	248	-02	-02	-00	7.
1.01	8.45	105	-06	-06	-05	20.	1.01	20.45	249	-02	-02	-00	7.
1.01	8.50	106	-06	-06	-05	20.	1.01	20.50	250	-02	-02	-00	7.
1.01	8.55	107	-06	-06	-05	21.	1.01	20.55	251	-02	-02	-00	7.
1.01	9.00	108	-06	-06	-05	21.	1.01	21.00	252	-02	-02	-00	7.
1.01	9.05	109	-06	-06	-05	21.	1.01	21.05	253	-02	-02	-00	7.
1.01	9.10	110	-06	-06	-06	21.	1.01	21.10	254	-02	-02	-00	7.
1.01	9.15	111	-06	-06	-06	21.	1.01	21.15	255	-02	-02	-00	7.
1.01	9.20	112	-06	-06	-06	21.	1.01	21.20	256	-02	-02	-00	7.
1.01	9.25	113	-06	-06	-06	21.	1.01	21.25	257	-02	-02	-00	7.
1.01	9.30	114	-06	-06	-06	21.	1.01	21.30	258	-02	-02	-00	7.
1.01	9.35	115	-06	-06	-06	21.	1.01	21.35	259	-02	-02	-00	7.
1.01	9.40	116	-06	-06	-06	21.	1.01	21.40	260	-02	-02	-00	7.
1.01	9.45	117	-06	-06	-06	21.	1.01	21.45	261	-02	-02	-00	7.
1.01	9.50	118	-06	-06	-06	21.	1.01	21.50	262	-02	-02	-00	7.
1.01	9.55	119	-06	-06	-06	22.	1.01	21.55	263	-02	-02	-00	7.
1.01	10.00	120	-06	-06	-06	22.	1.01	22.00	264	-02	-02	-00	7.
1.01	10.05	121	-06	-06	-06	22.	1.01	22.05	265	-02	-02	-00	7.
1.01	10.10	122	-06	-06	-06	22.	1.01	22.10	266	-02	-02	-00	7.



1.01	10.15	123	.06	.06	.01	22.	1.01	22.15	267	.02	.02	.00	7.
1.01	10.20	124	.06	.06	.01	22.	1.01	22.20	268	.02	.02	.00	7.
1.01	10.25	125	.06	.06	.01	22.	1.01	22.25	269	.02	.02	.00	7.
1.01	10.30	126	.06	.06	.01	22.	1.01	22.30	270	.02	.02	.00	7.
1.01	10.35	127	.06	.06	.01	22.	1.01	22.35	271	.02	.02	.00	7.
1.01	10.40	128	.06	.06	.01	22.	1.01	22.40	272	.02	.02	.00	7.
1.01	10.45	129	.06	.06	.01	22.	1.01	22.45	273	.02	.02	.00	7.
1.01	10.50	130	.06	.06	.00	22.	1.01	22.50	274	.02	.02	.00	7.
1.01	10.55	131	.06	.06	.00	22.	1.01	22.55	275	.02	.02	.00	7.
1.01	11.00	132	.06	.06	.00	22.	1.01	23.00	276	.02	.02	.00	7.
1.01	11.05	133	.06	.06	.00	22.	1.01	23.05	277	.02	.02	.00	7.
1.01	11.10	134	.06	.06	.00	22.	1.01	23.10	278	.02	.02	.00	7.
1.01	11.15	135	.06	.06	.00	22.	1.01	23.15	279	.02	.02	.00	7.
1.01	11.20	136	.06	.06	.00	22.	1.01	23.20	280	.02	.02	.00	7.
1.01	11.25	137	.06	.06	.00	22.	1.01	23.25	281	.02	.02	.00	7.
1.01	11.30	138	.06	.06	.00	22.	1.01	23.30	282	.02	.02	.00	7.
1.01	11.35	139	.06	.06	.00	22.	1.01	23.35	283	.02	.02	.00	7.
1.01	11.40	140	.06	.06	.00	23.	1.01	23.40	284	.02	.02	.00	7.
1.01	11.45	141	.06	.06	.00	23.	1.01	23.45	285	.02	.02	.00	7.
1.01	11.50	142	.06	.06	.00	23.	1.01	23.50	286	.02	.02	.00	7.
1.01	11.55	143	.06	.06	.00	23.	1.01	23.55	287	.02	.02	.00	7.
1.01	12.00	144	.06	.06	.00	23.	1.02	0.00	288	.02	.02	.00	7.
SUM 31.33 29.46 1.87 11164.													
( 796.31 748.31 48.34 316.13)													

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
545.	127.	39.	39.	11153.
15.	4.	1.	1.	316.
CFS	24.05	29.41	29.41	29.41
CMS	610.89	746.95	746.95	746.95
INCHES	63.	77.	77.	77.
AC-FT	77.	95.	95.	95.
THOUS CU M				

# HYDROGRAPH AT STA00001 FOR PLAN 1, RTIO 1

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
272.	63.	19.	19.	5577.
8.	2.	1.	1.	158.
CFS	12.03	14.70	14.70	14.70
CMS	305.45	373.47	373.47	373.47
INCHES	31.	38.	38.	38.
AC-FT	39.	47.	47.	47.
THOUS CU M				

# HYDROGRAPH AT STA00001 FOR PLAN 1, RTIO 2

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
327.	76.	23.	23.	6692.
9.	2.	1.	1.	189.
CFS	14.43	17.64	17.64	17.64
CMS	366.54	448.17	448.17	448.17
INCHES	38.	46.	46.	46.
AC-FT	46.	57.	57.	57.
THOUS CU M				

# HYDROGRAPH AT STA00001 FOR PLAN 1, RTIO 3

CMS 15. 3. 1. 1. 300.  
 INCHES 22.85 27.94 27.94 27.94  
 MM 580.35 709.60 709.60 709.60  
 AC-FT 60. 73. 73. 73.  
 THOUS CU M 74. 90. 90. 90.

# HYDROGRAPH AT STAGCC001 FOR PLAN 1, RTIO 9

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME  
 CFS 545. 127. 39. 11153.  
 CMS 15. 4. 1. 316.  
 INCHES 24.05 29.41 29.41 29.41  
 MM 610.89 746.95 746.95 746.95  
 AC-FT 63. 77. 77. 77.  
 THOUS CU M 77. 95. 95. 95.

\*\*\*\*\*

## HYDROGRAPH ROUTING

### ROUTED FLOWS THRU RESERVOIR 11608

STAG	ICOMP	IECON	IIAPE	JPLI	JPRF	INAME	ISTAGE	IAUTO
000002	1	0	0	2	0	1	0	0
ROUTING DATA								
QLUSS	CLOSS	AVG	IRFS	ISAME	IOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSIPS	NSIDL	LAG	AMSK	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	-1018.	-1	
STAG	1018.00	1019.50	1019.70	1020.50	1021.00	1022.00	1023.00	1024.00
FLOW	0.00	140.30	327.40	737.80	1084.00	1912.00	2988.00	4227.00
SURFACE AREA = 0. 4. 6. 15.								
CAPACITY = 0. 32. 45. 245.								
ELEVATION = 995. 1018. 1020. 1040.								
CREL	SPWID	COOM	EXPM	ELEV	COQL	CAREA	EXPL	
1018.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	

SURFACE AREA = 0. 4. 6. 15.  
 CAPACITY = 0. 32. 45. 245.  
 ELEVATION = 995. 1018. 1020. 1040.

#### UAM DATA

TINEL	COQD	EXPD	DAMPID
1019.7	2.9	1.5	425.
0.	52.	195.	360.
1019.7	1019.9	1020.0	1020.2
1019.7	1019.9	1020.0	1020.4
1019.7	1019.9	1020.0	1020.6
1019.7	1019.9	1020.0	1021.0
1019.7	1019.9	1020.0	1025.0

STATION 000002, PLAN 1, PATIL 1

0.60 PMF

END-OF-PERIOD HYDROGRAPH ORIGINATES



1. AK 001101 1, 189. AT TIME 15.02 HOURS

PLATE D-11

STATION 000002

0.	40.	80.	120.	160.	200.	240.	280.	C.	0.	0.	0.	0.	0.
0.05													
0.10													
0.15													
0.20													
0.25													
0.30													
0.35													
0.40													
0.45													
0.50													
0.55													
1.00													
1.05													
1.10													
1.15													
1.20													
1.25													
1.30													
1.35													
1.40													
1.45													
1.50													
1.55													
2.00													
2.05													
2.10													
2.15													
2.20													
2.25													
2.30													
2.35													
2.40													
2.45													
2.50													
2.55													
3.00													
3.05													
3.10													
3.15													
3.20													
3.25													
3.30													
3.35													
3.40													
3.45													
3.50													
3.55													
4.00													
4.05													
4.10													
4.15													
4.20													
4.25													
4.30													
4.35													
4.40													
4.45													
4.50													
4.55													
5.00													
5.05													
5.10													
5.15													
5.20													
5.25													
5.30													
5.35													
5.40													
5.45													
5.50													
5.55													
6.00													
6.05													
6.10													
6.15													
6.20													
6.25													
6.30													
6.35													
6.40													
6.45													
6.50													
6.55													
7.00													
7.05													
7.10													
7.15													
7.20													
7.25													
7.30													
7.35													
7.40													
7.45													
7.50													
7.55													
8.00													
8.05													
8.10													
8.15													
8.20													
8.25													
8.30													
8.35													
8.40													
8.45													
8.50													
8.55													
9.00													
9.05													
9.10													
9.15													
9.20													
9.25													
9.30													
9.35													
9.40													
9.45													
9.50													
9.55													
10.00													

6.65 571	
6.60 581	
6.55 591	
6.50 601	
6.45 611	
6.40 621	
6.35 631	
6.30 641	
6.25 651	
6.20 661	
6.15 671	
6.10 681	
6.05 691	
6.00 701	
5.95 711	
5.90 721	
5.85 731	
5.80 741	
5.75 751	
5.70 761	
5.65 771	
5.60 781	
5.55 791	
5.50 801	
5.45 811	
5.40 821	
5.35 831	
5.30 841	
5.25 851	
5.20 861	
5.15 871	
5.10 881	
5.05 891	
5.00 901	
4.95 911	
4.90 921	
4.85 931	
4.80 941	
4.75 951	
4.70 961	
4.65 971	
4.60 981	
4.55 991	
4.50 1001	
4.45 1011	
4.40 1021	
4.35 1031	
4.30 1041	
4.25 1051	
4.20 1061	
4.15 1071	
4.10 1081	
4.05 1091	
4.00 1101	
3.95 1111	
3.90 1121	
3.85 1131	
3.80 1141	
3.75 1151	
3.70 1161	
3.65 1171	
3.60 1181	
3.55 1191	
3.50 1201	

10.00120	0
10.05121	0
10.10122	0
10.15123	0
10.20124	0
10.25125	0
10.30126	0
10.35127	0
10.40128	0
10.45129	0
10.50130	0
10.55131	0
11.00132	0
11.05133	0
11.10134	0
11.15135	0
11.20136	0
11.25137	0
11.30138	0
11.35139	0
11.40140	0
11.45141	0
11.50142	0
11.55143	0
12.00144	0
12.05145	0
12.10146	0
12.15147	0
12.20148	0
12.25149	0
12.30150	0
12.35151	0
12.40152	0
12.45153	0
12.50154	0
12.55155	0
13.00156	0
13.05157	0
13.10158	0
13.15159	0
13.20160	0
13.25161	0
13.30162	0
13.35163	0
13.40164	0
13.45165	0
13.50166	0
13.55167	0
14.00168	0
14.05169	0
14.10170	0
14.15171	0
14.20172	0
14.25173	0
14.30174	0
14.35175	0
14.40176	0
14.45177	0
14.50178	0
14.55179	0
15.00180	0





20.15263.10  
 20.20264.10  
 20.25265.10  
 20.30266.10  
 20.35267.10  
 20.40268.10  
 20.45269.10  
 20.50270.10  
 20.55271.10  
 21.00272.10  
 21.05273.10  
 21.10274.10  
 21.15275.10  
 21.20276.10  
 21.25277.10  
 21.30278.10  
 21.35279.10  
 21.40280.10  
 21.45281.10  
 21.50282.10  
 21.55283.10  
 22.00284.10  
 22.05285.10  
 22.10286.10  
 22.15287.10  
 22.20288.10  
 22.25289.10  
 22.30290.10  
 22.35291.10  
 22.40292.10  
 22.45293.10  
 22.50294.10  
 22.55295.10  
 23.00296.10  
 23.05297.10  
 23.10298.10  
 23.15299.10  
 23.20300.10  
 23.25301.10  
 23.30302.10  
 23.35303.10  
 23.40304.10  
 23.45305.10  
 23.50306.10  
 23.55307.10  
 24.00308.10






60,418

STATION 000002

INFLOW (1), CATHEDRAL AND OBSERVED FLOW (2)













PLAN FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

CONVECTION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS									
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9	
				.50	.60	.70	.75	.80	.85	.90	.95	1.00	
DEVELOPED AT	000001	.05 (.13)	1	272. ( 7.71)	327. ( 9.25)	381. (10.79)	408. (11.56)	436. (12.34)	463. (13.11)	490. (13.88)	517. (14.65)	545. (15.42)	
RECEIVED IN	000002	.05 (.13)	1	189. ( 5.34)	233. ( 6.59)	276. ( 7.81)	297. ( 8.42)	319. ( 9.03)	346. ( 9.79)	377. (10.67)	406. (11.49)	434. (12.28)	

# SUMMARY OF DAM SAFETY ANALYSIS

PLATE 1 .....	RATIO OF PPE	ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM		TIME OF FAILURE HOURS
		STORAGE OUTFLOW	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	MAX CUTFLOW	TIME OF FAILURE HOURS	
	.50	1019.25	1019.25	0.00	40.	189.	0.00	15.92	0.00	0.00
	.60	1019.40	1019.40	0.00	41.	233.	0.00	15.83	0.00	0.00
	.70	1019.53	1019.53	0.00	42.	276.	0.00	15.83	0.00	0.00
	.75	1019.60	1019.60	0.00	42.	297.	0.00	15.83	0.00	0.00
	.80	1019.67	1019.67	0.00	43.	319.	0.00	15.83	0.00	0.00
	.85	1019.74	1019.74	.04	43.	346.	.17	15.83	0.00	0.00
	.90	1019.79	1019.79	.09	43.	377.	.17	15.83	0.00	0.00
	.95	1019.85	1019.85	.15	44.	406.	.33	15.83	0.00	0.00
	1.00	1019.90	1019.90	.20	44.	434.	.33	15.83	0.00	0.00

DA  
FILM  
O